

## Instructions for Conducting this Radon Test in Progress

**Radon Testers, Inc.**    The home of "Radon Ron"    **630.260.0700**    [www.RadonRon.com](http://www.RadonRon.com)    [radonron@mac.com](mailto:radonron@mac.com)

With your permission, a screening measurement to test for radon gas concentration is being conducted in your home. Potential purchasers, lenders and other interested parties will be making decisions pending the outcome of this radon test.

In order to obtain a valid measurement during this sampling period, it is essential that the following **Closed Building Conditions be maintained for the entire testing period** of at least 48 hours.

Please contact us with questions, and thank you for your understanding and patience!

-*"Radon Ron"*

**630.260.0700** Please live normally within requirements . Most people find it extremely easy to abide by Closed Building Conditions.



**We set up the house in accordance with the following conditions.**

**Please maintain these conditions for the duration of the test.**

<p><b>Closed Building</b> Conditions began 12 hours prior to the beginning of the test. The test will be a minimum of 48 hours. It will end upon retrieval of the radon testing equipment by a licensed <b>Radon Testers, Inc.</b> employee.</p>	<p><b>Closed Building</b> Conditions did not begin until the beginning of the radon test. The test will be extended an additional day and the first 12 hours of data will be excluded from the average.</p>
<p>Tamper-evident seals may have been placed on the windows in the testing locations. Removal or breaking of the seals will invalidate the test.</p>	<p style="text-align: center; color: blue; font-weight: bold; font-size: 1.2em;">NOTE:</p> <p>Closed Building Conditions must be maintained until the radon testing equipment is retrieved. Failure to abide by these conditions will invalidate the measurement.</p>

Please notify Radon Testers, Inc. immediately if any Closed Building Conditions requirements have not been maintained.

Zip Code: \_\_\_\_\_

Email/Fax: \_\_\_\_\_

\_\_\_\_\_  
(Please Sign) Signature of Responsible Party:

<b>Please Read the Following Testing Requirements and Sign this Sheet:</b>	
All windows in the house (including upstairs) should be kept closed during the whole measurement. Tamper-evident stickers have been placed on the windows. They must be intact upon retrieval or the test will be invalid.	
All exterior doors need to be kept closed. Normal entry and exit is permitted. (Shut door behind you).	
HVAC systems should be used with the fan in AUTO mode. The system should be between 67 - 77 degrees F. Whole house fans are not to be used.	
Ceiling fans, dehumidifiers, and air filters that are not built-in equipment to the house should not be operated within 20 feet of the radon testing equipment.	
Fireplaces should not be used during the test period. The flu should be kept closed.	
Clothes dryers, range hoods and bathroom fans should be used in moderation. 2 - 3 loads of laundry per day is considered normal.	
If a radon mitigation system is already installed in the house, it needs to have been running for at least 24 hours prior to and during the testing period.	
Like in hospitals where electronic devices are prohibited due to the interference they create, it is best to keep all cellular phones that are in use (receiving or transmitting a call) at least 5 feet away from all of the radon monitors being deployed.	

THE EQUIPMENT WILL BE PICKED UP ON \_\_\_\_\_.